- a factor of safety may also be allowed for vehicles travelling the closure below the signed speed limit, and
- if more than two traffic control stations (one each end) are in operation, depending on the operating characteristics of the roadworks site, the time for each queue to be released and travel through the roadworks site may need to be considered and included.

The 'maximum stopping time' value will be used in Table 4.3 to determine the multipliers to be used with the number and type of vehicle (average or heavy) from the five minute count or calculation.

Table 4.4(a) – Maximum spacing for repeater PREPARE TO STOP signs

Speed (km/h)*	Distance (m)
≤55	60
≥56	180

* The 'Speed' value to be used for the maximum spacing for repeater PREPARE TO STOP signs is the actual posted speed (temporary or permanent) which applies (this will generally be 60 km/h but may be less) where the repeater spacing is required. If the speed limit changes within a repeater spacing, use the spacing for the lower speed limit.

Note: The 200 m zone in Figure 2.2 does not apply.

Table 4.4(b) – Minimum distance from ROADWORK AHEAD or variable message sign to primary PREPARE TO STOP sign

Speed (km/h)^	Distance (m)
≤55	30
≥56–65	90
≥66–75	140
≥76–85	240
≥86	Four times the speed (km/h)

^The 'Speed' value to be used for the minimum distance from the ROADWORK AHEAD or variable message sign to the primary PREPARE TO STOP sign is the actual permanent posted speed of the road prior to any reduction for the roadworks.