

Item (Generic / Site Specific)		Risk Event	Consequence	Pre-treatment Risk			Treatment	Residual Risk			
				L	C	RR		L	C	RR	
3.2.	9	2 G	Traffic Management Personnel or workers reduce the advanced warning spacing, particularly speed reduction signage, due to unplanned hazards or obstructions causing insufficient warning of works for road users resulting in serious injury or fatality.	Serious injury or fatality to workers or Traffic Control as a result of insufficient advanced warning of approaching hazards.	C	4	H12	Traffic Management Personnel must risk assess the placement of signs and devices if the recommendations of the TGS are unsuitable. Adjustments to sign spacing must be as per the tolerances, where further adjustments are required prior approval must be sought. All adjustments must be recorded within the daily diary.	D	4	M8
3.2.	9	3 G	Project Delivery Supervisor or Traffic Management specifier do not have the required qualifications to select correct Traffic Guidance Scheme causing unnecessary risks to Traffic Management Personnel and Workers resulting in serious injury or fatality.	Serious injury or fatality.	C	4	H12	The Traffic Guidance Schemes in this suite are categorised by the recommended level of qualification and experience. Project Delivery Supervisor must ensure that they have appropriate qualification or experience or seek additional advice from a suitably qualified individual.	D	4	M8
3.2.	9	4 G	Traffic Management Personnel do not have the required qualifications or experience to implement the proposed Traffic Guidance Scheme causing unnecessary risks to Traffic Management Personnel and Workers resulting in serious injury or fatality.	Serious injury or fatality.	C	4	H12	Project Delivery Supervisor or Site Supervisor to ensure that suitably trained and experience Traffic Management Personnel are used to setup the site. Where this cannot be achieved, works may need to be postponed to a later date. Refer to section 7 for the minimum qualifications for each TGS.	D	4	M8
3.2.	9	5 G	Individual Works Crews or non-dedicated Traffic Management Crews lacking required qualification or experience to implement static setups causing unnecessary risks to Workers resulting in serious injury or fatality.	Serious injury or fatality.	C	4	H12	Project Delivery Supervisor or Site Supervisor to ensure that where Individual Works Crews are used that they select the appropriate drawings outlined in Section 7. Where additional static setups are required, dedicated Traffic Management Personnel must be used.	D	4	M8
3.2. 10		Lane Closure Impacts									
3.2.	10	1 G	Restrictions placed on lane capacities could cause an increase in congestion and delays resulting in adverse public reaction.	Adverse public reaction.	C	3	M9	Detailed traffic analysis to be undertaken prior to the implementation of any works. Site supervisor and Traffic Management Personnel to monitor on-site congestion for the duration of the works. Project Delivery Supervisor to undertake Pre-communication plan developed to distribute traffic to surrounding roads during works as required. Works to be undertaken when volumes are within allowable limits.	D	3	L6