

Item (Generic / Site Specific)		Risk Event	Consequence	Pre-treatment Risk			Treatment	Residual Risk				
				L	C	RR		L	C	RR		
3.2	14	10	G	Vehicles overtaking large trucks or other vehicles (unaware of pilot vehicle) during convoy operations and colliding with the worksite resulting in serious injury or fatalities to personnel.	Serious injury or fatality.	C	4	H12	Pilot vehicle to have flashing beacons and required signage to make obvious the convoy arrangements. ‘DO NOT OVERTAKE’ signage to be installed prior to reversible flow operation and where overtaking is observed, periodically through the setup as a repeater. Delineation of the worksite to be provided where possible to provide some advance warning of the worksite. Pilot vehicle driver to monitor vehicles in convoy and radio workers where a breach may occur. Workers to ensure they always have adequate escape routes.	D	4	M8
3.2.		15	Short Term Low Impact Setups									
3.2.	15	1	G	Short Term Low Impact setups varying from acceptable levels of worksite protections, based on well documented and understood static worksite practices causing unnecessary risks to workers resulting in serious injury or fatality.	Serious injury fatality.	C	4	H12	Measures required to implement a static setup, particularly at works that are short term in nature may expose staff implementing Temporary Traffic Management to a higher level of risk exposure. All personnel prior to the commencement of works are to ensure that a detailed risk assessment, outlining potential hazards and mitigation is completed in line with AGTTM Part 5 - Short Term Low Impact procedures. The risk assessment must determine if the works can be completed safely under the proposed Short Term Low Impact setups. Where the risk assessment determines unsafe practices, a static setup must be implemented.	D	4	M8
3.2.	15	2	G	Implementation of Short term Low Impact setups in live traffic lanes reducing the capacity of the road causing excessive congestion and delays resulting in adverse public reaction.	Adverse public reaction.	C	3	M9	Due to the 'short term' and 'low impact' nature of the works the congestion and delays are expected to be minimal. Detailed Traffic Management analysis outlining the predicted impacts on the surrounding road network must be completed prior to implementation. Where congestion is observed on site, the works should be postponed to maintain traffic flow on the network.	D	3	L6