

4.1.3 Temporary Speed Zones

Temporary speed limits will follow the guidance within Section 5.5 of AGTTM Part 3, table 5.5 Length of temporary speed zone and the Main Roads Code of Practice. These details will vary depending on the project, location, and stage of the works. The Traffic Management Assessor or Delivery Supervisor must provide details of temporary speed zones, how speed will be managed at the site, dates, and times.

For afterhours work, the posted speed limit should be reinstated, and the site left clean and free of debris. If this cannot be achieved, appropriate signage, temporary pavement markings and speed zones should be considered. Any afterhours temporary speed zones must comply with standards and guidelines and may need prior approval or notification to the relevant Road Infrastructure Manager.

Where the minimum or maximum length of temporary speed zones exceeds the recommendations in AGTTM, a variation with RTM and Road Infrastructure Manager approval must be provided. Where the posted speed of the road is equal to or Lower than 70km/h, the lowest speed reduction must be switched with intermediate signage to ensure the speed reduction is placed at a distance of L3 from the Hazard (Refer table below)

Table 14: placement of temporary speed limit – MRWA CoP Table 6

Approach Speed (km/h)	Works Area Speed (km/h)	L3 (m)
70	60	70
	40	70
60	40	45

4.1.4 Existing Traffic signals

The Traffic Management Assessor or Delivery Supervisor will assess the impacts of proposed temporary Traffic Management setups on existing signalised intersections. These details will vary depending on the project, location, and stage of the works.

Where any of the following criteria is met, the 0922-01532-Complex Traffic Management Plan must be used:

- Alteration to the function of the traffic signals or sign display.
- Closure of a traffic lane where:
 - Within a signalised intersection
 - Within 30m of the stop line on the approach
 - Within 30m of the adjacent stop line on the departure
- Closure of any part of a signalised dedicated turning lane.

Refer to the Main Roads Signal Approval Policy for more details.

4.1.5 Impact on Adjoining Road Network

Traffic flow and network stability should be maintained wherever possible. The Traffic Management Assessor or Delivery Supervisor must provide details and mitigation techniques for impacts on the adjoining road network. The details will vary depending on the project, location, and stage of the works. Where significant congestion or delays are predicted at the planning stage, prior Road Infrastructure Manager and/or RTM approval may be required prior to the implementation of any Traffic Management devices.