

Scenario 4 cont.		
Road Number	Road Name	Locality
H059	Willinge Drive	Entire (Following completion of BORR)
H069	Ocean Reef Upper Swan Highway (Also: Ocean Reef Road, Gngara Road)	Wangara to Tonkin Hwy (SLK 8.07 -17.77)
M023	Pinjarra Road	Entire
M074	Lakeland Lake Clifton Road (Also: Mandjoogoodap Drive, Mandurah Road, Dawesville Bypass, Old Coast Road)	Freeway to Dawesville (SLK 0 -27.4)
H009	South West Highway (Also: Robertson Drive)	Forrest Highway to Bussell Highway (SLK 153.10 – 154)

Scenario 5 – Works on high speed/volume multilane roads on the Main Roads network

Criteria		Yes/No
1	The work area occupies the live traffic lane.	
2	The work area is not separated by a full road closure or road safety barrier.	
3	The permanent posted speed limit is 100km/h or more.	
4	The road is a multilane road.	

4.6 Consultation and Communication/Notification

4.6.1 Other Agencies

In accordance with the CoP., notification to all relevant agencies is required using the 'Notification of Road Works Form' attached at Appendix 'A'.

4.6.2 Public

A comprehensive public notification of the works and traffic management arrangements that will effect journey times may be required. Additional notification requirements shall be actioned upon request by impacted stakeholders and/or the Road Infrastructure Manager prior to the execution of these works where required.

The below are pre-communication methods which may be utilised, but may not be required for all projects:

- Notice to Motorists in the Newspaper placed [1] two weeks in advance, [2] one week in advance and [3] at the commencement of works;
- Letter drop to all residents and businesses within the traffic control zone one week ahead of the scheduled works; and,
- VMS boards installed 5 days prior to the works.
- Significant projects will require radio advertising.

4.7 Temporary Pavement Markings

Installation of temporary pavement markings may be required after each individual stage of works prior to the application of the ultimate pavement marking in accordance with the following:

- After profiling works, delineation of lanes shall be via temporary RRPMS.
- On completion of asphalt works, delineation of lanes shall be by either ultimate pavement markings, temporary RRPMS or temporary painted pavement markings.
- The installation of temporary RRPMS shall be at not less than 4m spacing and not greater than 12m spacing.