

A shadow vehicle should be considered for every scenario however, based on a risk assessment may be omitted as part of mobile inspections or grading works.

During the installation of signs and where there are workers on foot, position a lookout person adjacent to the worker so that they can view approaching traffic. The lookout person must warn workers to vacate the roadway before the arrival traffic. The recommended distance from the lookout person to approaching traffic is shown in the below table.

Table 36: AGTTM Part 5 Section 4.5.5 Table 4.11: Sight Distance for Lookout Person

Speed (km/h)	Distance (m)
≤ 45	80
46 – 55	100
56 – 65	120
66 – 75	140
76 – 85	160
86 – 95	180
96 – 110	200
>110	220

4.8.1.6 Works off Road – Shoulder, Medians, Verges and Footpaths with Workers on Foot or Small Plant

This practice may be used where the works are completely off the road and involve workers on foot or small items of plant. This works must be contained within the shoulder, median, verge or footpath and must not encroach into live traffic lanes. Refer to AGTTM Part 5 Section 5.1 – Shoulders, Medians, Verges and Footpaths with Workers on Foot or Small Plant Items Only and **0922-01531-STLI-012** and **0922-01531-STLI-016 to 018**.

This practice is best suited to the following tasks (does not include all tasks):

- Mowing, tilling, seeding, weed spraying.
- Litter or graffiti removal.
- Garden maintenance.
- Minor tree clearing.
- Herbicide spraying.
- Minor cleaning of culverts, pipes, and pits.
- Road edge guidepost installation/repairs.
- Street light maintenance.
- Footpath repairs.

Where all workers are exclusively behind a safety barrier, are working clear of the deflection zone for the existing system and are not visible to traffic, temporary traffic management may not be required. The typical Temporary Traffic Management requirements for this works may include advanced warning signs and a vehicle mounted warning device on the works vehicle.