

6.2.2.3 Traffic Management Assessor

The Traffic Management Assessor is responsible for providing any additional Traffic Management related advice for the proposed works. The Traffic Management Assessor should work closely with, may be in the same role as or may be engaged by the Delivery Supervisor to ensure the safe and timely delivery of the works. This may include but is not limited to:

- Selecting appropriate Traffic Guidance Schemes to be used to protect works.
- Site Specific Traffic Management sign and device requirements.
- Proposed times and hours of works to comply with traffic analysis.
- Traffic volumes and traffic data analysis.
- Use and requirements of additional Traffic Management devices such as PTCs or TMAs.
- Additional Risk Assessment provided at the planning stage.
- Traffic Management staging requirements.
- Pedestrian / Cyclists management.
- Aftercare arrangements.
- Requirements for Notification of Roadworks.

6.2.2.4 Delivery Supervisor

The Delivery Supervisor must have the ultimate responsibility to ensure that the Traffic Management Plan, including all associated Traffic Guidance Schemes have been selected to cover the scope of the works and identifies all measures required for safe delivery of the works. This role may be completed by multiple individuals, including members from the Road Infrastructure Manager role to ensure the delivery of the works. The Delivery Supervisor is responsible for the following:

- Ensuring they have the appropriate authorisation from the Road Infrastructure Manager.
- Ensuring they have an approved and accepted Traffic Management Plan, including all associated Traffic Guidance Schemes before commencing works.
- Hold a BWTM Accreditation if selecting a TGS for Implementation
- Ensuring that the selected Traffic Guidance Schemes cover the proposed worksite conditions.
- Ensuring that there is an approved copy of the Traffic Management Plan, including all associated Traffic Guidance Schemes available on site (digital copies are accepted).
- Ensuring any Temporary Speed Zones have appropriate approval.
- Obtaining approval and timings for occupation of the worksite from the Road Infrastructure Manager, prior to commencing work.
- Operating in terms of the applicable traffic regulations.
- Ensuring that the Traffic Management and work teams are supported in matters of safety.
- Ensuring that all Traffic Management and work personnel are suitably trained and qualified for the works.
- Ensure that a suitable number of work personnel are in place to apply, maintain and remove the Traffic Management devices and to facilitate the works.
- Arranging and recording details of inspections of Temporary Traffic Management measures.
- Arranging for the publication of approved notices in appropriate media as specified by the Traffic Management advice.
- Ensure suitable communication and consultation with the affected stakeholders is always maintained.
- Review feedback from field inspections, worksite personnel and members of the public, and take action to amend the traffic control measures as appropriate following approval from the Road Infrastructure Manager.