

6.2.2.4.1 Roadworks Traffic Manager

The Roadworks Traffic Manager is responsible for ensuring that plans involving 'Complex Traffic Arrangements', particularly in the Metropolitan Region and as defined in the Main Roads Code of Practice, will be reviewed and endorsed prior to works commencing. The Roadworks Traffic Management must ensure the following:

- Receive the fully compiled Traffic Management Plan, including all associated Traffic Guidance Schemes and any further Traffic Management documentation or advice from the Delivery Supervisor.
- Recommend any changes/additions to the proposed Traffic Management documentation and setups to the Delivery Supervisor.
- Send the signed and endorsed Traffic Management documentation, once reviewed to the Delivery Supervisor.
- Be contacted where on-site changes are required that are outside the scope of an AWTM risk assessment using the risk assessment matrix provided in this Traffic Management Plan.
- Endorse on-site changes where required, all changes are to be noted in the daily diary by the Traffic Management Supervisor and copies forward to the Roadworks Traffic Manager once the shift is complete.
- Suspend/stop the works where the on-site changes are deemed dangerous or unfit for purpose.

6.2.2.5 Site Supervisor

The Site Supervisor is responsible for overseeing the day-to-day activities and the practical application of the proposed Traffic Management staging. The Site Supervisor is responsible for the following:

- Instruct workers on the relevant safety standards, including the correct wearing of high visibility safety vests and night-work safety requirements
- Ensure traffic control measures are implemented and maintained as per the relevant/selected Traffic Guidance Scheme.
- Undertake and submit the required inspection and evaluation reports to management.
- Render assistance to road users and stakeholders when incidences arising out of the works affect the network performance or the safety of road users and workers.
- Take appropriate action to correct unsafe conditions, including any necessary modification to selected Traffic Guidance Schemes with the scope of their qualification and as per the Main Roads Code of Practice.

6.2.2.6 Traffic Management Supervisor

The Traffic Management Supervisor is responsible for the practical application of the Traffic Management devices and personnel in accordance with the appropriate Traffic Guidance Schemes, AGTTM, Main Roads Code of Practice and AS 1742.3. The Traffic Management Supervisor is responsible for the following:

- Prior to any implementation activities on site the Traffic Management Supervisor must execute all actions outlined in the [Austroads Guide to Temporary Traffic Management Part 6, Field Staff – Implementation and Operations](#).
- Ensuring the Traffic Management devices are set out in accordance with the Traffic Guidance Schemes, AGTTM and Main Roads Code of Practice.
- Ensure that the quality and quantity of Traffic Management devices matches the relevant Traffic Guidance Scheme, Main Roads Code of Practice and AS 1742.3.
- Have all relevant qualifications, including Worksite Traffic Management for complex Traffic Management arrangements.
- Must be on site to manage variations, contingencies and emergencies and take overall responsibility for the implemented Traffic Management setups.