

7.2 Sequence and Staging

7.2.1 Traffic Guidance Schemes Installation General

TTM measures must be installed, maintained, and removed in a planned and safe manner. Prior to commencing, the Traffic Management Implementers must check and review the approved Traffic Management Plan / Traffic Guidance Schemes, the worksite, and the proposed activity to ensure they are complementary and are appropriate. This section provides best principles and practices guidance. The Traffic Management Implementers must check the road environment, especially the “on the day” traffic flows, to ensure that it is at an appropriate level for the Temporary Traffic Management intended. A 5-minute count of traffic should provide an appropriate estimate of volumes to reference against values recorded in the Traffic Management Plan or the Traffic Guidance Schemes.

If the worksite and the approved Traffic Management Plan and Traffic Guidance Schemes are not complementary, before occupying the worksite the Traffic Management Implementer must determine whether they can:

- make compliant adjustments (e.g. lengthen taper within tolerances) to the Traffic Guidance Schemes
- contact the Delivery Supervisor, Roadworks Traffic Manager or Traffic Management Designer to approve relevant modifications (e.g. additional signs or distances outside of tolerances) to the Traffic Guidance Schemes.
- contact the relevant Road Infrastructure Manager traffic control facility to initiate actions identified on the Traffic Guidance Schemes to be taken (e.g. change in the VMS, Variable Speed Limit Signs or Lane Usage Signage).

Where the Traffic Management Plan and Traffic Guidance Schemes cannot be suitably adjusted or modified, the Traffic Management Implementer should advise the Delivery Supervisor that they are not appropriate, and the works should be postponed.

All adjustments and authorised modifications are to be recorded on the Traffic Management Plan and Traffic Guidance Schemes or on-site record.

7.2.2 Typical Installation Principles

Installation is typically carried out applying one of the processes in accordance with AGTTM Part 5 as “short term – low impact works” to protect the Temporary Traffic Management staff. The examples in this section are based on limiting high risk manoeuvres during installation including U-Turns and loops exposing workers to live traffic without protection.

Fundamental principles that should be complied with to ensure safety during this work activity are that:

- travel should only be in a forward direction on any road
- the Temporary Traffic Management vehicle may be used as added protection considering the:
 - availability of safe park up area(s) near the signage placement location
 - line of sight to approaching vehicles
 - visibility of the worker and Temporary Traffic Management vehicle to approaching vehicles
 - location of signage/devices on vehicle which need to be accessed
 - worker access to vehicle (e.g. not through crush zones)
 - available space on road shoulder or median
 - geometry/terrain of shoulder or median
 - distance between vehicle and travel path / shoulder drop off
 - Traffic Management Implementer proximity to ‘expected travel path while traversing between vehicle and signage location
 - likely area in which the vehicle may move if impacted
 - availability of ‘gaps in traffic’ or lookout