

- in addition to minimum widths between physical constraints, other mitigations may be implemented including:
 - the availability of response vehicles to remove broken down vehicles to maintain traffic flow
 - alternative routes or detours may also be an option, especially for emergency vehicles

Emergency services must be advised in advance of any constrained road environment likely to impact their response times and route choice.

3.3.6 Speed management plan

New

Requirements for a speed management plan are included in the Transport and Main Roads Technical Specification [MRTS02 Provision for Traffic](#), and for projects not subject to the requirements of MRTS02, the requirements of MRTS02 may be adopted.

3.3.7 Speed enforcement

New

Requirements for planned speed enforcement are included in the Transport and Main Roads Technical Specification [MRTS02 Provision for Traffic](#), and for projects not subject to the requirements of MRTS02, the requirements in MRTS02 may be adopted.

Also consider the specific signing requirements for speed enforcement activities in QGTTM Part 3 Section 5.5.4 *Speed enforcement*.

3.3.8 End-of-queue treatments

New

End-of-queue risk control measures, in accordance with Chapter 1, Clause 2 of the [Guideline – Traffic Management at Works on Roads](#) must be used if required by QGTTM Part 3, Section 4.8.3.

End-of-queue risk control measures may also be triggered by the requirements in Clause 6.5.7 of the Transport and Main Roads Technical Specification, [MRTS02 Provision for Traffic](#) or nominated as mandatory control measures in Clause 5.8 of Annexure MRTS02.1

For projects not subject to the requirements of MRTS02, the requirements in MRTS02 may be adopted.