

2 Design Process

2.2 Risk Assessment

Difference

Replace:

It is important to note that a Design Exceptions Report must be approved by the relevant Road Infrastructure Manager (RIM) and road authority if design exceptions are made or published standards or the AGTTM are not adhered to.

with:

Where variations to the treatments in the Queensland MUTCD Part 3 or QGTTM are proposed, a risk assessment certified in accordance with the requirements of Clause 1.9 of Queensland MUTCD Part 3 must be undertaken.

2.5 Essential Design Principles

2.5.3 Signs

Difference

Replace the following dot point:

- signs that are not relevant during works must be removed or covered as it is essential that all signs at the worksite or varied travel route accurately represent the prevailing conditions at all times.

with:

- vehicle-mounted signs that are not relevant (during works or after works) must be removed or covered as it is essential that all vehicle-mounted signs accurately represent the prevailing conditions at all times.

Addition

It is important to consider the impact of existing static signs on the mobile works operations and while it may not always be practicable or possible as part of mobile works operations to remove or cover existing static signs, any existing static signs which may cause conflict or a safety issue for the mobile works operations should be treated, especially if the mobile works operation is stationary for a period. Subject to a risk assessment, existing static signs along a route may remain in place during mobile works operations.