

The vehicle mounted warning device should be mounted as high as practicable on the vehicle for best visibility to all road users (e.g. on the roof (cab) of the truck). This helps to ensure the device is not obscured (e.g. overhanging vegetation, raised truck body, permanent signs). It may be moved near the rear of the vehicle if a roof-mounted sign could be obscured by a load.

While the requirements in this document apply once published, Transport and Main Roads recognises that making immediate changes to flashing lamps on inspection vehicles may require a greater lead in time to ensure compliance.

In recognition of this, inspection vehicles (other than those used for emergency or other infrequent use) must comply with the requirements in item (b) by 31 July 2027.

3.5 Lookout protection method

New

For requirements and further information on the Lookout Protection Method, refer to the [Guideline – Traffic Management at Works on Roads](#).

3.6 Combining different works protection methods

New

Combining different works protection methods at the one site is permitted where the requirements for the different works protection methods are met.

Different short-term low-impact provisions may be used for different activities when appropriate and when satisfying the risk assessment and other provisions and criteria at the one work site.

Short-term low-impact provisions may be used when appropriate and when satisfying the risk assessment and other provisions and criteria on a static work site where the temporary traffic management arrangements at the static work site are in place and required for other work activities. The static site must not be created solely for enabling a speed reduction which would permit short-term low-impact work protection methods which require a lower speed limit than applies to be used.

Where appropriate, and when satisfying the risk assessment and other provisions and criteria, short-term low-impact provisions may be used as part of a mobile work site.

Signs and devices used in static works sites or for mobile works must be installed in accordance with the requirements of QGTTM Part 3 or Part 4 respectively.