

with

Note: *These distances are based on a maximum distance of 3.5 m between road workers' location and their escape to a shoulder or median. For longer escape routes additional sight distance will be required and the sight distance provisions for the Lookout Protection Method, in the [Guideline – Traffic Management at Works on Roads](#) must be applied.

5 Works outside of traffic lane

5.1 *Shoulders, medians, verges and footpaths with workers on foot or small plant items only*

5.1.3 Traffic control devices

Addition

In the subsection '**Advance warning signs**', add the following:

The Worker (symbolic) may be omitted when workers on foot are either

1. not visible to traffic, or
2. visible and located greater than 6 m clear of traffic, or
3. located outside the road reserve.

Difference

In the subsection '**Vehicle mounted warning device**', replace entire subsection with the following:

Refer to Section 3.4 for vehicle-mounted warning device requirements.

5.1.4 Pre-installation processes

Difference

Replace 3rd dot point:

- Confirm TGS has been signed off by relevant personnel, with a copy of the TGS onsite at all times during the works.

with:

- If a TGS is provided, confirm TGS has been signed off by relevant personnel, with a copy of the TGS onsite at all times during the works.