

5.1.5 Installation (TGS instruction)

Difference

In the subsection '**Set-out**', replace:

All signs and devices must be placed as shown on the TGS. Advance signs are to be located a distance as per Table 2.3 from the start of the worksite or hazard.

Vehicles used to install signage and equipment must have a yellow flashing lamp(s) that is visible to all approaching traffic.

Before any equipment or materials are brought onto the work area, a drive through check of the work site traffic management set up should be made in all directions, including all side roads if required. This is to confirm that the work area is safe for all workers and road users, and signs and devices are placed as indicated on the TGS.

with:

A TGS is not required but may be developed for shoulders, medians, verges and footpaths with workers on foot or small plant items only activities. If provided, all signs and devices must be placed as shown on the TGS.

Advance signs are to be located a distance as per Table 2.3 from the start of the worksite or hazard.

Vehicles used to install signage and equipment must, at a minimum, have a yellow flashing lamp(s) visible to all approaching traffic.

Before any equipment or materials are brought onto the work area, a visual check of the worksite traffic management set up (vehicle-mounted warning devices and signs are in place, and sight distance requirements are met) should be made in all directions, including all side roads and property accesses if required. This is to confirm that the work area is safe for workers and road users, and signs and devices are placed as required by this section, or as indicated on the TGS (if provided). This may require a drive-through check.

Difference

In the subsection '**Operation**', replace:

See AS 1742.3 for more information

with:

Guidance on the placement of signs is given in the QGTTM Part 6 Section 6.6.2 and Queensland MUTCD Part 3 Clause 4.3.2.