

2.6.8 Departures from standards and innovation

The requirements and recommendations set out in this Guide should not be used to prevent innovative or alternative traffic management solutions that provide improved outcomes (including safety and value for money), which meet the intent of this Guide.

Where innovative treatments are proposed to be adopted for use by traffic controllers, undertake a risk assessment in accordance with the traffic management plan and include the innovative treatment as approved by the TMP designer and road authority.

2.7 When a Traffic Controller Gets to the Worksite

2.7.1 General

As part of on-site traffic controlling tasks, traffic controllers may be responsible for setting up the designated worksite. The traffic control station set up and positioning must be in accordance with the guidelines specified in Part 3 of the AGTTM.

If traffic control is taken over part way through a shift, the traffic controller must check that all signs and devices are properly set up at the start of their shift.

2.7.2 Pre-start meeting

The contractor and the traffic management company must to organise a pre-start meeting, to be attended by the traffic controller/s before commencing traffic control duties. The meeting is vital to ensure everyone on site understands activities that are occurring and the responsibilities and roles of each person working on the site are made clear prior to work commencing. Matters to cover in the pre-start meeting include:

- direct briefing of traffic controller's role
- details of traffic guidance scheme, including traffic controller escape path
- contact numbers and details of relevant people
- breaks (e.g. toilet, water)
- traffic monitoring instructions
- details of the works being undertaken
- locations where workers are on foot
- site specific risks
- consideration of an exclusion zone
- incident management procedures.

2.7.3 Station set up and positioning

The traffic control station position must be established after due consideration is given to the following:

- is the station clear of the travel path?
- does the traffic controller feel safe?
- does the traffic controller have an escape path? An area around the traffic control station must be kept clear in advance, behind and along the escape path
- the traffic controller has required line of sight of approaching traffic (see Section 2.7.4)