

Figure 4.8(a) – Queued traffic ahead multi-message sign assembly



Where this assembly is used, the preferred method of display is to locate the QUEUED TRAFFIC AHEAD text panel (TM1-46A) closest to traffic.

6. A ROADWORK AHEAD sign, or VMS must be placed as per Table 4.4(b) in advance of the primary PREPARE TO STOP sign position discussed in Step 5, except for advance signs on side roads, where the requirement of Step 9 will apply.
7. Surges in traffic demand can occur so adequate monitoring of the queue must be undertaken to minimise the risk of end-of-queue collision. If the end of queue extends beyond the estimated end-of-queue position, adequate warning of the end of queue must be provided. The options available include:
 - a) initially, when traffic queues are approaching the estimated end-of-queue position, the traffic controllers should advise the site supervisor that traffic queues are approaching their maximum length and contingency planning may need to be implemented
 - b) as an interim measure, the traffic controllers may adjust their timing or give priority to one approach to minimise queuing from the key direction
 - c) if adjusting timings is not successful in managing queue lengths, implement a pre-designed contingency plan to cater for the longer queue lengths being experienced – this will need to be completed by the traffic management implementer while traffic controllers continue to control traffic, and