

Item (Generic / Site Specific)		Risk Event	Consequence	Pre-treatment Risk			Treatment	Residual Risk			
				L	C	RR		L	C	RR	
3.2.	3	3 G	The interaction of work personnel with through traffic may cause an increase of conflicts resulting in serious injury or fatality.	Serious injury or fatality.	C	4	H12	The Traffic Guidance Schemes outline the requirements and positioning for delineation and devices in accordance with the AGTMM. Table 4.1 AGTMM Part 3 details the requirements for edge clearances and protection. Site supervisor to conduct daily toolbox meetings outlining dangers of working around live traffic.	D	4	M8
3.2.		4	Special Events / Other Works / Other Notification and Approvals								
3.2.	4	1 G	Temporary Traffic Management setups during events and/or other projects causing unexpected impacts on the road network resulting in adverse public reaction.	Adverse public reaction.	C	4	H12	Prior notification including details of each work stage, dates and times must be provided to the Local Government Authority or Road Infrastructure Manager prior to the commencement of works. Details should be entered into the Road Space Booking System and those responsible for the delivery of the works must check for conflicts. Where significant issues are identified in the planning phase, the Traffic Management Assessor or Project Delivery Supervisor must detail these impacts and mitigating procedures as part of the Traffic Management Advice.	D	4	M8
3.2.	4	2 G	Works scheduled during event and/or other projects causing conflicts with proposed Traffic Management setups resulting in minor delays to business activities.	Minor delays to business activities. 5% to 10% Variation in KPI or objective.	C	2	L6		D	2	L4
3.2.		5	Emergency Services / Emergency Arrangements / Contingencies								
3.2.	5	1 G	Lack of Temporary Traffic Management setups to manage hazards or risks at an Emergency causing unnecessary exposure for workers and road users resulting in serious injury or fatality.	Serious injury or fatality.	C	4	H12	The Emergency Works drawings are to be used as an initial mitigation to hazards and risks. Where mitigation is required for an extended period of time the Emergency Works Scenario Temporary Traffic Management is to be replaced with suitable static setups.	D	4	M8