

Item (Generic / Site Specific)		Risk Event	Consequence	Pre-treatment Risk			Treatment	Residual Risk			
				L	C	RR		L	C	RR	
3.2.	5	2 G	Timely selection and organisation of Temporary Traffic Management signs and devices in an emergency scenario causing unnecessary exposure for road users resulting in serious injury or fatality.	Serious injury or fatality.	C	4	H12	Project Delivery Supervisor with consultation with the Road Infrastructure Manager is to ensure prudent measures are implemented to cover emergency scenarios. Works and Traffic Management Crews must be briefed on the procedures and policies required in an emergency scenario prior to any works commencing. Where possible, the minimum level of traffic management devices required in an emergency scenario must be easily dispatched to an emergency location.	D	4	M8
3.2.	5	3 G	Restrictions and delays associated with the traffic control causing a failure to respond for emergency services resulting in an increase severity in emergencies.	Failure to respond to emergencies.	C	4	H12	Pre-communication for all emergency services prior to the implementation of any works via the Notification of Roadworks. This will include, any proposed detours and predicted increases in congestion. Where safe, workers and Traffic Control to respond to emergency services to facilitate an unhindered passage through or around the worksite.	D	4	M8
5	4	G	Dangerous goods, damage to services or failure of services causing restricted access through the worksite resulting in adverse public reaction.	Adverse public reaction.	B	3	H12	Should any incident arise involving vehicles transporting dangerous goods, damage or failure of services; all work shall cease immediately, machinery and vehicles turned off and the area cleared of personnel as soon as possible. Traffic Management Personnel (and other personnel if necessary) to ensure no vehicles or pedestrians enter the hazardous area. All personnel will understand safety briefs on evacuation and control procedures before entering the site.	D	3	L6