

Item (Generic / Site Specific)		Risk Event	Consequence	Pre-treatment Risk			Treatment	Residual Risk		
				L	C	RR		L	C	RR
3.2. 6		Existing Temporary and Permanent Signage & Permanent Structures								
3.2. 6	1 G	Existing signage and structures causing reduced visibility of the worksite and temporary traffic control resulting in serious injury or fatality.	Serious injury or fatality.	C	4	H12	Opaque material is required to cover contradictory signage during the temporary traffic management setup. Site supervisor and Traffic Management Personnel will ensure all contradictory signage is covered. Where signs cannot be covered and conflict with temporary signage, they will be removed. To accommodate structures on the road, Traffic Management Supervisor can extend/shorten up to 25% of specified dimensions. Site Supervisor to record changes in the daily diary.	D	4	M8
3.2. 6	2 G	Defective temporary signage causing inadequate advanced warning of proposed works resulting in serious injury or fatality.	Serious injury or fatality.	C	4	H12	Site supervisor and Traffic Management Personnel will ensure sign integrity with periodic site inspections. Retro-reflective signage is required during night works.	D	4	M8
3.2. 7		Excavations Adjacent to Live Traffic								
3.2. 7	1 G	Excavations or above ground hazards associated with the works being inadequately protected causing an increase of property damage resulting in adverse public reaction and medical treatment or Lost Time Injury	Adverse public reaction and medical treatment or Lost Time Injury	C	3	M9	The Traffic Management Assessor or Project Delivery Supervisor must consider the impact of longitudinal depressions and above ground road hazards adjacent to live traffic lanes during the work and where left unattended prior to the installation of any devices. Refer to Section 4.1.9 and Table 16 of this TMP for more details.	D	3	L6