

Item (Generic / Site Specific)		Risk Event	Consequence	Pre-treatment Risk			Treatment	Residual Risk			
				L	C	RR		L	C	RR	
3.2.	15	3 G	Works requiring additional time or extending beyond a single shift causing unsafe conditions for workers and increased congestion and delays resulting in serious injury or fatality.	Serious injury or fatality.	D	4	M8	The works must adhere to the times specified on the drawings and within AGTTM Part 5 Short Term Low Impact Table 3.1: Types of Short Term Low Impact Works. A risk assessment must be undertaken prior to works commencing to determine if the works can be done within the times allocated. Where the works may extend beyond the time, a static worksite must be implemented.	E	4	L4
3.2. 16		Mobile Works Impacts									
3.2.	16	1 G	Mobile work convoys within live traffic lanes reducing the capacity of the road causing excessive congestion and delays resulting in adverse public reaction.	Adverse public reaction.	C	3	M9	Detailed Traffic Management analysis outlining the predicted impacts on the surrounding road network must be completed prior to implementation. Where congestion is observed on site, the works convoy may pull off the road in a safe location to allow vehicles to pass and then the works resumed. Where major impacts occur consideration should be given to postponing the works to a time where volumes are reduced.	D	3	L6
3.2.	16	2 G	Motorists not expecting work vehicle in live lane causing an increase of rear end crashes at the worksite resulting in serious injury or fatality.	Serious injury or fatality.	C	4	H12	Advanced warning vehicle, shadow vehicle and lead vehicle to be utilised as required to form a mobile works convoy to protect the works vehicle. Works vehicle to maintain the worksite clearances provided on the Traffic Guidance Scheme.	D	4	M8
3.2.	16	3 G	Workers on foot within mobile convoy having minimal protection from approaching traffic causing unnecessary risks to workers resulting in serious injury or fatality.	Serious injury or fatality.	C	4	H12	Where workers are on foot and within the mobile convoy they must comply with the worksite clearances provided on the Traffic Guidance Schemes. Temporary 40km/h speed reductions should be implemented where there is high risk of workers coming in contact with road users. Workers on site must be suitably qualified, experience and equipped to perform the works under a mobile works convoy. Where this cannot be achieved, a static worksite should be provided.	D	4	M8