

vehicles through the worksite. Where facility access cannot be maintained, detours via adjacent accesses or other mitigating procedures must be implemented to ensure no significant impacts occur.

4.2.7 Rail Crossings

The Traffic Management Assessor or Delivery Supervisor must determine the impacts to the rail crossing and other facilities and provide suitable approvals and notification. Where using the Rail Approach (Traffic Guidance Schemes TMC-RA), prior rail infrastructure notification and/or approval must be sought. Where site specific constraints do not permit the safe application of the Traffic Guidance Schemes, then a site-specific plan is to be prepared and approved by the Road Infrastructure Manager. Any requirements for a Rail Safety Management Plan (RSMP) will be instructed by the rail infrastructure manager prior to the implementation of any works. Table 3 of the Code of Practice provides distances from the railway level crossings within which the Rail Authority shall be notified via a version of the 'Notification of Road Works Form' in appendix 'A'.

Table 18: Distance from Railway Level Crossing – MRWA CoP Table 3

Speed Limit (km/h)	Distance from Railway (m)
<70	150
70 to 90	200
>90	300

Traffic Controllers should take special care at rail crossings as motorists will generally follow their directions when differing from other signals or devices. Where a rail crossing exists within a section being controlled by a Traffic Controller, a flag person with the relevant Track Access Permit should be stationed at the traffic stop line of the railway crossing at least 3m from the nearest rail. Flag Person must be equipped with a two-way radio and are to watch for trains, advising Traffic Controllers with enough time to stop traffic before the train approaches.

Where the section of traffic control is to one side of the railway level crossing, but within the distances above, the flag person stationed at the railway level crossing shall be stationed on the same side of the crossing as the section under traffic control, at the stop line or at least 3m from the nearest rail. The flag person must be equipped with a hand-held stop / slow sign that has the rear 'slow' side covered. The flag person must ensure that vehicles do not queue through the rail level crossing by stopping motorists prior.

All personnel within the rail corridor must wear orange, fluorescent clothing as per the Safe working Rules on all rail networks. Traffic Controllers operating stop/slow within the vicinity of rail crossing should have the slow side of the bat covered to avoid conflicts with existing boom gates/barriers.

4.2.8 School Crossings

The Traffic Management Assessor or Delivery Supervisor must ensure that no significant impacts occur to school crossings within the vicinity of the works. Where works are adjacent or near schools, they should be planned where work hours are outside school pick up and drop off hours to avoid excessive congestion and delays during the increase in traffic. The affected schools should be notified via the Notification of Roadworks detailing actual work hours and dates.

Any aftercare arrangements are to ensure that the site does not interfere with normal day use of pedestrian crossings, particularly crossings around schools. Facilities must be left without significant hazards and surface condition at crossings must meet normal use expectations.

4.2.9 Special Events and Other Works

Prior notification including details of each work stage, dates and times must be provided to the Local Government Authority or Road Infrastructure Manager prior to the commencement of works. Details