

should be entered into the Road Space Booking System and those responsible for the delivery of the works must check for conflicts.

Conflicts to the worksite include but are not limited to; adjacent events causing unforeseen increases in traffic or impacts to the worksite, adjacent worksite causing conflicting traffic management advice, conflicting detours from other sites causing adverse public reactions from motorists becoming lost or unforeseen increases in traffic through the site and heavy or oversized vehicles needing access through the worksite.

Where significant issues are identified in the planning phase, the Traffic Management Assessor or Delivery Supervisor must detail these impacts and mitigating procedures as part of the Traffic Management Advice.

4.2.10 Emergency Vehicle Access

The Traffic Management Assessor or Delivery Supervisor must ensure that emergency services have continual access through or around the worksite during the proposed works. Personnel must be on-site to render assistance to emergency services and significant delays should be avoided. Where significant issues may occur on site, notification must be provided to emergency services prior the commencement of any works. The Notification of Roadworks should be used to notify Emergency Services with details of work nature, location, date and times, and any on-site contacts. Where required police communications may be requested to render assistance to a site where significant speed occurs.

4.3 Night Works Provisions

The Traffic Management Assessor or Delivery Supervisor must detail the requirements for additional lighting or night works provisions. In areas where there is no street lighting and Traffic Management activities become high risk without proper illumination, additional lighting towers should be provided.

All Traffic Controllers and/or workers installing light towers for night works shall have suitable training and/or qualification to undertake the work activity. These persons shall conduct a risk assessment prior to operating any lighting tower, to consider potential environmental factors including but not limited to, overhead power lines.

All signs used at night are to be Class 1 Retro-reflective material and delineation will be either retro-reflective or be sufficiently illuminated. All personnel shall wear high visibility clothing suitable for night works and traffic controllers must use night wands when directing traffic.

4.4 Road Safety Barriers

The proposed Traffic Management arrangements does not utilise temporary road safety barrier setups. Where temporary road safety barrier setups are required, a site-specific Traffic Management Plan should be provided with all required details. Where the works requires the removal or replacement of permanent road safety barrier that is preventing potentially catastrophic outcome the 0922-01532-Complex Plan must be used, refer to section 4.4 Road Safety Barriers of that plan.

4.5 Shadow Vehicles

The shadow vehicle provides close protection to the rear of work vehicles and workers on foot. The shadow vehicle must be used to protect workers on foot where the below scenarios are met, and the road has the following traffic volumes.

- All work on roads with traffic volumes that exceed 15,000 vpd.
- Night works on roads that exceed 2,000 vpd.