

Equipment or materials which are brought onto the work area should be unloaded from the non-traffic side of a stationary work vehicle. The required advanced warning signs, to be erected by workers, should be done so in a manner that does not expose workers to oncoming traffic. Install signs so that the nearest edge is clear of the travelled path of vehicles and so that the signs are clearly visible to all oncoming vehicles.

4.8.2 Class 2 Mobile Convoys

This practice may be used where the works convoy is travelling greater than 20km/h below the permanent speed limit (work vehicles travelling at 70km/h or less in a 100km/h speed zone or 40km/h in a 70km/h speed zone) and there are no workers on foot. This work must be under a mobile convoy that cannot stop in live traffic lanes and vehicles must be at least the size of a standard utility vehicle. Refer to AGTTM Part 4 Section 3.2.2 Class 2 and **0922-01531-MS2-001** to **019**.

This practice is best suited to the following tasks (does not include all tasks):

- Linemarking using ride-on plant, self-propelled towed or pushed.
- Operation of pavement test vehicles.
- Raised pavement marker installation
- Pavement sweeping.
- Pavement testing.
- Road inspections.
- Snow clearing/spreading grit.
- Shoulder grading.
- Vegetation control (mowing and spraying).

Scenarios provided in the TGS cover a single work vehicle slowly moving on the verge to mobile convoys closing multiple lanes, involving shadow, tail, and advanced warning vehicles. The scenarios provide separate mobile temporary speed zones depending on clearance between the work vehicle and live traffic lanes. Distances between each vehicle in the mobile works convoy, excluding the shadow vehicle, are shown in the table below:

Table 44: AGTTM Part 4 Section 3.6 Table 3.1: Spacing Distance Between Vehicles in Mobile Works

Speed (km/h)	Distance (m)
≤ 45	50
46 – 55	70
56 – 65	90
66 – 75	110
76 – 85	140
86 – 95	160
96 – 105	200
> 106	230

Any signs or devices required for the proposed works must be attached to the vehicles within the convoy. Where works are being undertaken on two-way roads, signs or devices required must be displayed on both ends of the vehicle to warn road users from the opposite direction. All vehicles within the mobile works convoy must be fitted with a vehicle mounted warning device which must not be obscured during the works.