

6. SAFETY PLAN

6.1 Occupational Safety and Health

All persons and organisations undertaking these works or using the roadwork site have a duty of care under statute and common law to themselves, their employees, and all site users, lawfully using the site, to take all reasonable measures to prevent accident or injury.

This Traffic Management Plan forms part of the overall project Safety Management Plan and provides details on how all road users considered likely to pass through, past, or around the worksite safely and efficiently will be managed for the full duration of the site occupancy and works.

6.2 Roles and Responsibilities

6.2.1 Responsibilities

The Site Supervisor has the ultimate responsibility to ensure that the Traffic Management Plan and associated Traffic Guidance Schemes, is installed correctly for the prevention of injury and property damage to employees, contractors, sub-contractors, road-users, and all members of the public. The Site Supervisor, through the pre-start meeting, shall communicate to all staff the need to mitigate risks and hazards on the worksite, including maintaining escape routes from traffic and plant at all times.

The Delivery Supervisor will ensure all site personnel are fully aware of their responsibilities, and that traffic controllers are appropriately trained and accredited. The Delivery Supervisor must ensure that sufficient controllers are available to ensure appropriate breaks are taken.

The works must not commence or continue until all signs, devices and barricades are in place and operational in accordance with the requirements of this Traffic Management Plan and associated Traffic Guidance Schemes.

Traffic Management personnel must ensure that the number, type and location of signs, devices and barricades are as per the relevant Traffic Guidance Schemes, Traffic Management Advice, Main Roads WA Code of Practice, AGTTM and AS 1742.3. Should a situation arise that is not covered by this Traffic Management Plan, the Road Infrastructure Manager shall be notified.

The Road Infrastructure Manager may direct erection, relocation or removal of signs or devices, which in the opinion of the Road Infrastructure Manager, are not in accordance with this Traffic Management Plan and do not provide sufficient safety for road users. If not complied to, the Road Infrastructure Manager may arrange for erection, relocation or removal by others at the cost of the Contractor.