

- Where changes are required to complex Traffic Management arrangements, the Traffic Management Supervisor must risk assess those changes and record variations in the Daily Diary. Where an RTM is not consulted, all changes must be within the original scope and objectives of the proposed Traffic Guidance Schemes. All other changes must be endorsed by the RTM and must be authorised by the Road Infrastructure Manager.
- Ensure there is a copy of the approved Traffic Management Plan and all associated Traffic Guidance Schemes are available on site at all times.

6.2.2.7 Traffic Management Implementers, Traffic Control and Other TM Related Personnel

The Traffic Management Implementers and Other Traffic Management Related Personnel are responsible for the implementation of Traffic Management signage and devices to ensure a safe and compliant worksite. Traffic Controllers must be used to control road users to avoid conflict with plant, workers, traffic and pedestrians, and to stop and direct traffic in emergencies. The roles are responsible for the following:

- Operate in accordance Austroads Guide to Temporary Traffic Management Part 6 – Field Staff and Part 7 – Traffic Controllers.
- Have all relevant qualifications and licenses available on site as evidence of completion, including Basic Worksite Traffic Management and Traffic Control accreditations.
- Take appropriate breaks as required in Austroads Guide to Temporary Traffic Management Part 6 – Field Staff, Part 7 – Traffic Controllers and/or the relevant WS&H Regulations.
- Correctly wear high visibility vests, in addition to other protective equipment required (including night wands for night works).
- Comply with the requirements of the Traffic Management Plan, including all associated Traffic Guidance Schemes.
- Ensure no activity is undertaken that will endanger the safety of other workers or the public.
- Enter and leave the site by approved routes and in accordance with safe work practices.
- Take reasonable care for their own health and safety and of other persons.
- Always comply with the requirements of the traffic rules.
- Be aware of the general configuration of signs and devices and report a defect to the Traffic Management Supervisor.
- Record all incidents and complaints at the worksite to the Traffic Management Supervisor and Site Supervisor, to be notified to the Delivery Supervisor or Road Infrastructure Manager as required.
- At least one accredited person with Basic Worksite Traffic Management must remain on site with the responsibility of ensuring the traffic management devices are set out in accordance with the TMP.

6.3 Personal Protective Equipment

All personnel entering the work site shall correctly wear high visibility vests to AS/NZS 4602, in addition to other protective equipment required on a site-by-site basis (e.g. protective footwear, eye protection, helmet, sun protection, respiratory devices etc.) at all times whilst on the worksite.

6.4 Plant and Equipment

All plant and equipment at the workplace shall meet statutory requirements and have the required registration, licences or certification where required. All mobile equipment shall be fitted with suitable reversing alarms. All mobile plant and vehicles shall be fitted with a pair of rotating flashing yellow lamps in accordance with AS1742.3 clause 4.14.1. All workers are aware of the safe work practice at the time of the site induction.