

- Indicate intention to enter the traffic stream using direction indicators;
 - Ensure there is a suitable gap from oncoming traffic to allow for a safe entry manoeuvre; and,
 - Turn off the rotating yellow lamp(s) once driving at 40 km/h speed limit.
- When in close proximity to intersections performance of entry and exit manoeuvres are not to be completed. Work personnel shall not cross traffic streams on foot unless necessary.

Both construction and traffic management vehicles are required to only park within the work area indicated on the Traffic Guidance Scheme as the work area. Vehicles shall not obstruct paths and be parked an adequate distance from intersections or driveways to ensure clear sight lines remain for all road users.

7.5 Communicating Traffic Management Plan Requirements

The requirements of the Traffic Management Plan and all associated Traffic Guidance Schemes must be communicated on-site by either the Delivery Supervisor or Site Supervisor prior to the implementation of any Temporary Traffic Management Devices.

A site-specific risk assessment must be completed prior to the works commencing considering:

- The action plans for the residual risks from the Traffic Management Plan.
- The site conditions.
- Existing Traffic Management infrastructure such as electronic devices and ITS.
- The installation procedure.
- The operation of the TGSs once implemented.
- The removal procedure.
- The possibility of the setup being left unattended.

The risk assessment needs to be relevant to the type of traffic E.G:

- The volume of traffic.
- The speed of traffic.
- The duration of work.
- The type of work.
- Heavy haulage
- Wide loads
- PTA Buses

This risk register and site-specific assessment must form part of the Temporary Traffic Management Toolbox Talks. All persons involved with Temporary Traffic Management activities must be briefed/inducted by the Traffic Management Supervisor and have the documented on the site records. The primary objective of the Toolbox Talks is to explain the following to Temporary Traffic Management staff:

- Key aspects of the Traffic Management Plan.
- Identify any site-specific hazards.
- Temporary Traffic Management requirements for the worksite.
- Safe workplace requirements and limits.