

A		B		C		D		E		F		G		H		NOTES	
STAGE 4:												IMPLEMENTATION PROCEDURES				DOCUMENTATION ON-SITE VARIATIONS MUST BE APPROVED BY THE TRAFFIC MANAGEMENT SUPERVISOR, THAN AN ON-SITE VARIATION MADE AND CHANGES RECORDED IN THE DAILY DAIRY. FOR MORE INFORMATION REFER TO SECTION 9.3 OF THE TMP. 1. TM VEHICLE SHALL BE ANY OF THE FOLLOWING: 1.1. TRAFFIC MANAGEMENT UTE 1.2. UTE WITH ARROW BOARD 1.3. CONE TRUCK 1.4. MR TRUCK 1.5. HR TRUCK 1.6. TRUCK MOUNTED ATTENUATOR 2. THIS DRAWING IS FOR IMPLEMENTATION ONLY AND MUST BE USED IN CONJUNCTION WITH AN APPROVED TRAFFIC MANAGEMENT LAYOUT TGS. 3. THIS DRAWING IS TO BE USED AS A GUIDELINE FOR THE TYPICAL FREEWAY CHICANE INSTALLATION AND MAY CHANGE DEPENDING SITE REQUIREMENTS. 4. TMA TO BE USED AS PER THE REQUIREMENTS SET OUT IN THE MAIN ROADS CODE OF PRACTICE AND THE 'MAIN ROADS WA - REQUIREMENTS FOR THE USE OF TRUCK MOUNTED ATTNUATORS (TMAs) IN WA'. 5. REFER TO MANUFACTURING ADVICE FOR SHUNT DISTANCES ON TRUCK MOUNTED ATTENUATORS. 6. APPROACH SIGNAGE IS INDICATIVE OF A GENERIC FREEWAY CHICANE SETUP AND MAY CHANGE ACCORDING TO SPECIFIC PLAN.	
												STAGE 4: 1. RAMP ACCESS RETAINED PRIOR TO GORE MARKING. 2. WORK CONVOY TO PREPARE TO EXTEND CONES THROUGH OFF RAMP AND ON MAIN APPROACH.					
STAGE 5:												STAGE 5:				FOR IMPLEMENTATION ONLY	
												STAGE 5: 1. TMA RELOCATES AFTER OPENING TO SHADOW TC AND WORK VEHICLE. 2. TMA TO SHADOW TM VEHICLE AND TC SETTING OUT REMAINING CONES ON MAIN ALIGNMENT AND RAMP ALIGNMENTS (IF REQUIRED).					
																LEGEND — EXISTING ROAD PROPOSED CONES — TC MOVEMENTS	
																 METROPOLITAN REGIONS TRAFFIC MANAGEMENT BRANCH WATERLOO CRESCENT TELEPHONE (08) 138 138 EAST PERTH 6004	
																DATE OF DRAWING 2025 JULY SCALE - LOCAL GOVERNMENT AUTHORITY - POSTED SPEED - ROAD AUTHORITY MAIN ROADS WA WORKSITE SPEED - CHECKED BY TYLER HARTLEY SIGNATURE Tyler Hartley ACCREDITATION RTM-0066 DESIGNED BY MICHAEL REED SIGNATURE Michael Reed ACCREDITATION AWTM-23-II536-02	
																GENERIC TRAFFIC GUIDANCE SCHEME IMPLEMENTATION WORK SETUPS CONTROL OF ACCESS CHICANE IMPLEMENTATION (2/2)	
																DRAWING NO 0922-01531-IW-006 REVISION 6	
A		B		C		D		E		F		G		H			