

3 Around the worksite

3.4 Road Closures

Difference

Replace the dot point:

- if the worksite blocks a side road a detour should be provided (see Section 3.8)

with the following:

- not all road closures will require a detour route to be installed, Section 3.8 includes the requirements and considerations when signing a detour route and the parameters for determining the need for signing a detour route.

3.6 Safety buffer

Difference

Replace the fourth paragraph:

A safety buffer must be provided immediately in advance of the work area where the speed is 60 km/h or higher. An area 20 m to 30 m in length is generally sufficient. However, if the work area is hidden from approaching traffic (e.g. by a crest or curve), the length of the safety buffer should be extended to a point which can be clearly seen by approaching traffic. On multilane roads, this may be increased up to 100 m.

with the following:

A safety buffer must be provided immediately in advance of the work area where the speed is 60 km/h or higher and either of the following apply:

- local traffic may continue beyond the detour point towards the work area (as indicated by Figure 3.2), or
- the work area is within 50 m of traffic at the detour point and traffic is travelling toward the work area before being detoured (see Figures 3.6(a), 3.6(b), 3.6(c) and 3.6(d) with the green zone indicating a safety buffer).

An area 20 m to 30 m in length is generally sufficient: however, if the work area is hidden from approaching traffic (for example by a crest or curve), the length of the safety buffer should be extended to a point which can be clearly seen by approaching traffic. On multilane roads, this may be increased up to 100 m.