

5. Fully sign the closure and provide some VMS signs near the closure but allow road users to use the existing current signage if adequate to direct them to their chosen destinations.
6. Fully sign the closure and provide some VMS signs near the closure and some additional VMS or other direction signs at key decision points along the various detour routes to supplement the existing current signage to direct road users to their chosen destinations.

When closing major links such as tunnels or bridges or arterial roads, advance warning of the closure at a point where drivers can easily choose an alternative route should be provided.

For closures and detour routes that are to be in place for an extended period or are frequently used, the use of a diversion route signing approach as per TRUM Volume 3 Part 9 may be considered. The diversion route signing approach may also be considered for short term detours or to provide clarity where multiple different detour routes exist or overlap.

3.8.1 Detours

Difference

Replace:

Detour markers must be erected at all subsequent changes of direction and intersections along the route to reassure road users they are on the correct path (e.g. detour in a built-up area through side streets) and they can continue their journey using permanent road sign information. This usually involves directing road users back onto their original route of travel at a point past the worksite. Signs must be erected for each direction of travel affected by the closure and checked to ensure all detour signs are prominently displayed with clear sight distance (see Section 2.5.3 Table 2.3).