

Temporary speed limits should only apply while the condition that makes them necessary exists, so remove temporary speed limit signs as soon as the necessity passes. For further details on signs see Section 2.5.3.

Guidance on the use of temporary variable speed limit signs in construction and maintenance work areas on motorways is given in the [Guideline – Traffic Management at Works on Roads](#).

5.5.2 Temporary speed humps

Addition

Guidance on the use of temporary speed humps and associated signage is given in the *Guideline – Traffic Management at Works on Roads*.

5.5.3 Rumble strips

Addition

Guidance on the use of rumble strips and associated signage is given in the *Guideline – Traffic Management at Works on Roads*.

5.5.4 Speed enforcement

New

Requirements for planned speed enforcement are included in [Technical Specification MRTS02 Provision for Traffic](#). Projects not subject to the requirements of MRTS02 may adopt the requirements in MRTS02.

Speed enforcement planned and undertaken in accordance with MRTS02 must include the [TC sign](#) SPEED CAMERAS USED AT ROADWORKS FOR ROAD SAFETY (TC2320_1, see Figure 5.5.4(c)) and must include an orange target board to the speed limit signs as per TC2320_2 for camera enforcement, or TC2320_3 for enforcement by a Roadways Behaviour Monitoring System (RBMS) camera. The orange target board must be added to all speed limit signs (including repeater and speed limit AHEAD signs) on approach to the enforcement location. The ROADWORK AHEAD sign (T1-1 or equivalent, such as a VMS) must be installed in advance of the site. The multi-message sign arrangements in Figures 5.5.4(a) and 5.5.4(b) must not be used for speed enforcement in accordance with MRTS02.

When speed enforcement is planned and undertaken outside the requirements of MRTS02, TC sign TC2361 must be used as follows:

- For enforcement by camera, use the multi-message sign arrangement in Figure 5.5.4(a).