

Difference

In the subsection '**Operation**', replace:

The preferred location of the work vehicle is parked adjacent to the works with the vehicle mounted warning device activated and parked clear of traffic lanes.

with:

The preferred location of the work vehicle is parked adjacent to the works with the vehicle mounted warning device activated and parked clear of traffic lanes or parked where parking would be legal, and the safety of other road users is not compromised.

5.2 Shoulders, medians, verges and footpaths with large plant items only

5.2.3 Traffic control devices

Addition

In the subsection '**Advance warning signs**', add the following:

The ROAD PLANT AHEAD sign may be omitted when all plant is either:

1. not visible to traffic, or
2. visible and located greater than 6 m clear of traffic, or
3. located outside the road reserve.

Difference

In the subsection '**Vehicle mounted warning device**', replace entire subsection with the following:

Refer to Section 3.4 for vehicle mounted warning device requirements.

5.2.4 Pre-installation processes

Difference

Replace 3rd dot point:

- Confirm TGS has been signed off by relevant personnel, with a copy of the TGS onsite at all times during the works.

with:

- If a TGS is provided, confirm TGS has been signed off by relevant personnel, with a copy of the TGS onsite at all times during the works.