

3 Roles and Responsibilities

3.3 *TTM Relationships*

3.3.3 TMI responsibilities for TTM on a worksite include:

Addition

Add the following dot point:

- reporting incidents and near misses.

6 TGS installation

6.5 *Positioning of signs and devices*

Difference

Replace:

- c) Edge of traffic lane to road safety barrier system:
 - i. 0.3 m for a posted speed limit during roadworks up to and including 40 km/h
 - ii. 0.5 m for a posted speed limit during roadworks 50 km/h to 60 km/h
 - iii. 1.0 m for a posted speed limit during roadworks 70 km/h to 80 km/h
 - iv. 2.0 m for a posted speed limit during roadworks greater than 80 km/h.

with:

- c) Edge of traffic lane to road safety barrier system:
 - i. 0.3 m for a posted speed limit during roadworks up to and including 40 km/h
 - ii. 0.5 m for a posted speed limit during roadworks 50 km/h to 80 km/h
 - iii. 1.0 m for a posted speed limit during roadworks greater than 80 km/h.

6.6 *Typical Locations for Signs*

6.6.1 Long term

Addition

Signs directed exclusively towards pedestrians must be securely installed at a height which will enable signs to be viewed easily by pedestrians (typically between 500 mm and 1000 mm above the footpath level to the underside of the sign).