

- d. the risks versus benefits associated with installing the signs for a detour route, and
- e. the potential confusion for road users who encounter the signs for a detour route but are not impacted by or aware of the road closure requiring a detour (especially relevant when closing a local street and using a higher order road as part of the detour route).

In addition to the above, detour routes should be provided when closing major links such as tunnels or bridges or arterial roads, and the following options for detour routes and signs for these links should be considered:

- 3. Fully sign the closure and the various detour routes based on likely destinations to be sought by road users.
- 4. Fully sign the closure and allow road users to use the existing current signage if adequate to direct them to their chosen destinations.
- 5. Fully sign the closure and provide some VMS signs near the closure but allow road users to use the existing current signage if adequate to direct them to their chosen destinations.
- 6. Fully sign the closure and provide some VMS signs near the closure and some additional VMS or other direction signs at key decision points along the various detour routes to supplement the existing current signage to direct road users to their chosen destinations.

When closing major links such as tunnels or bridges or arterial roads, advance warning of the closure at a point where drivers can easily choose an alternative route should be provided.

For closures and detour routes that are to be in place for an extended period or are frequently used, the use of a diversion route signing approach as per TRUM Volume 3 Part 9 may be considered. The diversion route signing approach may also be considered for short term detours or to provide clarity where multiple different detour routes exist or overlap.