

the maximum stopping time needs to include the total time from when the traffic controller stops traffic, through until the same traffic controller releases traffic for the next cycle from that approach. This would typically include the following considerations:

- the time taken for the traffic queue from one approach to pass the traffic control station and travel the length of the closure
- the time for the queue at the other end of the site to leave that traffic control station and also travel the length of the closure (this may commence at the same time as the other queue or following the completion of the other queues travel if shuttle flow is in operation)
- if traffic queues are held for a period (with no traffic traveling through or past the site), then this hold time will also need to be included
- a factor of safety may also be allowed for vehicles travelling the closure below the signed speed limit, and
- if more than two traffic control stations (one each end) are in operation, depending on the operating characteristics of the roadworks site, the time for each queue to be released and travel through the roadworks site may need to be considered and included.

The 'maximum stopping time' value will be used in Table 4.3 to determine the multipliers to be used with the number and type of vehicle (average or heavy) from the five minute count or calculation.

Table 4.4(a) – Maximum spacing for repeater *PREPARE TO STOP* signs

Speed (km/h)*	Distance (m)
≤55	60
≥56	180

* The 'Speed' value to be used for the maximum spacing for repeater *PREPARE TO STOP* signs is the actual posted speed (temporary or permanent) which applies (this will generally be 60 km/h but may be less) where the repeater spacing is required. If the speed limit changes within a repeater spacing, use the spacing for the lower speed limit.

Note: The 200 m zone in Figure 2.2 does not apply.